Sufficient quantity of proper jointing materials, gusset plates, bolts and nuts with washers, etc., complete., should be sent to enable the erection being done at site.

The staging 25 ft. high to support the above tank should consist of angle iron or channel iron stanchions with angle iron bracings of suitable dimensions and the stanchions should be provided with suitable base plate and foundation bolts, etc.

Proper section of main joists either channel or I beam with the top joists for supporting the tank should be included. The dimensions of the joists proposed to be used should be clearly specified.

The staging parts should be erected at the works and each part accurately numbered, so that they could be assembled at site easily. All the bolt holes should be accurately done.

A suitable ladder from the ground to the top of the tank should be included to facilitate climbing up the tank and all the necessary fixtures and struts to the same should be completely given.

It is preferable to provide gusset plates for the bracings instead of direct joints to the stanchions.

Two sets of correct working drawings with complete dimensions of all the parts should be sent to facilitate erection.

Time of delivery of the materials should be noted in the quotation and the period strictly adhered to. The drawings, however, should be sent well in advance.

The tank and the staging materials should be painted with a coat of red oxide paint before despatch.

Yours faithfully,
V. VEDAVYASACHARYA,
Secretary,
Stores Purchase Committee.

BANGALORE BUILDINGS DIVISION.

Notification, dated 19th December 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Buildings Division, up to 8th January 1934, (2 P.M.) for constructing Central Police Station, Fort, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees eight hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Central Police Station, Fort, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender witl rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality or works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of estimate of quantities for constructing Central Police Station, Fort, Bangalore.

No.	Items of work	Per	Quantity
1	Earth work excavation of foundation and filling in basement	C.yd.	563
2	Stone jelly concrete in lime mortar ...	C.ft.	7,238
3	Size stone in clay with bond stones at 6' apart ...	„	7,767
4	Burnt brick in clay ...	„	5,705
5	Burnt brick in mortar ...	„	2,059
6	Burnt stone slabs 6" thick with two line dressed to the exposed portion and champering edges of steps and basement slabs.	S.ft.	2,137
7	Reinforced concrete pillars with base and capital as per plan	R.ft.	300
8	Teakwood panelled doors with frame 4" x 5" with iron fittings with painting, etc., complete with iron clamps.	S.ft.	392
9	Teakwood lock-up doors with iron bars 1" dia. as per design, with iron clamps, with painting, etc., complete.	„	46
10	Teakwood windows with glazed shutters with iron bars ¾" dia. with painting,etc., with clamps.	„	680
11	Reinforced ornamental perforated ventilators ...	„	272
12	Rolled steel girders with cutting, hoisting and painting 3 coats, Tata's tested.	C.wt.	240·13
13	Roofing with Madras flat terrace with plastering, whitewashing, etc., complete.	Sqr.	44·46
14	Plain parapet wall as per design (burnt brick in mortar) ...	R.ft.	500
15	Ornamental balastrades parapet wall as per plan ...	„	20
16	Cornice 9" x 9" complete ...	„	520
17	Lime mortar plastering with three coats of whitewashing ...	Sqr.	141·56
18	Ornamental chunam panel and other works below window and wherever necessary.		
19	Cement pointing to basement with cut lines ...	„	13·48
20	Flooring with Cuddapah slabs 1½' thick over 3" concrete and cement pointing, etc., complete.	„	38·49
21	Chunam mortar name board with flag staff, etc., complete.		
22	Clearing site and levelling ground		
23	Painting doors and windows.		
24	Outlet pipes 2' long ..	Each	12
25	Rain water pipes		

Notification, dated 19th December 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 16th January 1934 (2 P.M.), for construction of a Workshop attached to the Fort High School, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissor. Notes, as earnest money, and be superscribed "Tender for construction of a Workshop attached to the Fort High School, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Buildings Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities for constructing a Workshop attached to the Fort High School, Bangalore.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs.		
1	Earthwork excavating foundation and filling in basement with watering and tamping.	C.yd.		170	
2	Burnt stone gelly concrete in lime mortar (1:1:2).	C.ft.		1,860	
3	Burnt stone in clay with bond stones 6' apart in foundation and basement.	"		2,795	
4	Burnt brick in clay ...	"		4,512	
5	Burnt brick in mortar ...	"		879	
6	Burnt stone slabs 6" thick one line dressed for inner, 2 lines for outer basement (old materials to be dressed to the required size and carted from old Sanskrit College.)	S.ft.		1,386	
7	Plastering with lime mortar ..	Sqr.		82·42	
8	Pointing the basement with cement cut lines.	"		4·93	
9	White and colour washing two coats.	"		87·35	
10	Cement perforated ventilators as per approved design.	S.ft.		176	
11	Steel trusses with two coats of approved paintings at 8¾ to 9 for 15' clear span.	Each		8	
12	Teakwood work wrought and put up including wood oiling 2 coats.	C.ft.		160·28	
13	Roofing with First class Mangalore tiles on teak reepers with two coats of wood oiling (old materials to be carted from the Sanskrit College.)	Sqr.		28·88	
14	Ridge tiles set in mortar with cement pointing, etc., complete (old being carted from the Sanskrit College).	R.ft.		150	
15	Teakwood eave boards 1" thick with paintings etc., complete (old being carted and fixed from the Sanskrit College.)	...		..	
16	Ornamental finials	Each		2	
17	Do pendants	"		4	
18	Sunshades with Mangalore Tiles on teakwood reepers with wood oiling complete.	"		3	
19	Architecture mouldings all round the buildings (4½" x 2").	R.ft.		189	

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs a. p.
20	Flooring with Kadapa slabs over 3" concrete bed with cement pointing (old slabs carted from old Sanskrit College).	Sqr.		14·36	
21	Teekwood windows 4' x 5½' with shutters and paintings with iron fittings, etc., complete (old ones being used from Sanskrit College)	S.ft.		418	
22	Teakwood doors with panelled shutters 4' x 7' with tower bolts iron fittings, etc., complete (old ones fixed from the Sanskrit College).	,,		140	
23	Rolled steel girders 12" x 5" with hoisting and fixing, etc., complete (Tata's tested).	Cwt.		29.00	

A. TANDONI RAO,
Executive Engineer.